BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Providing cement concrete roads to Yelahanka Janatha layout At Ward No.07

Agency:-Achutha Murthy K

SCHEDULE-B

Sl No	App Qty	Description of work	Approved Rates of Achutha Murthy K		
			Unit	Rate in Words	Rate in Figures
1	2	3	4	5	6
1	198	Removing B.S. slab of Drain and stacking and as per the direction of engineer in charge of work.	sqm	71.95	Rupees Seventy One And Paise Ninety Five Only
2	34.5	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications and as per the direction of engineer in charge of work.	cum	93.36	Rupees Ninety Three And Paise Thirty Six Only
3	158.4	Refixing stone slabs of drains and pointing in C.M and as per the direction of engineer in charge of work.	sqm	86.78	Rupees Eighty Six And Paise Seventy Eight Only
4	826.85	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications and as per the direction of engineer in charge of work.	cum	179.45	Rupees One Hundred Seventy Nine And Paise Forty Five Only
5	861.35	Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications and as per the direction of engineer in charge of work.	cum	107.56	Rupees One Hundred Seven And Paise Fifty Six Only
6	337.58	Construction of granular sub-base by providing close graded material, mixing in a mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method.Close graded granular sub-base material as per 400-1 For Grading- II Material and as per the direction of engineer in charge of work.	cum	1797.89	Rupees One Thousand Seven Hundred Ninety Seven And Paise Eighty Nine Only
7	337.58	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications and as per the direction of engineer in charge of work.	cum	5569.67	Rupees Five Thousand Five Hundred Sixty Nine And Paise Sixty Seven Only

Contractor

Executive Engineer
Project Division

Asst. Executive Engineer
Project Division
Yelahanka Zone
Bangalore

Sl No	App Qty	Description of work	Approved Rates of Achutha Murthy K		
			Unit	Rate in Words	Rate in Figures
1	2	3	4	5	6
8	39.6	Providing and fixing RCC precast Slabs of 0.10 m thick of CC 1:2:4 with 20 mm and down size graded granite metal , machine mixed , including cost of all material , labour , HOM of Machinery , curing complete and as per the direction of engineer in charge of work.	sqm	2266.45	Rupees Two Thousand Two Hundred Sixty Six And Paise Forty Five Only
9	337.58	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) M20 for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, for raft foundation, column footing, main and secondary beams with all lead and lifts etc.,complete (exclusive of cost of steel and fabrication charges.) and as per the direction of engineer in charge of work.	cum	6726.78	Rupees Six Thousand Seven Hundred Twenty Six And Paise Seventy Eight Only
10	2250.5	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift and as per the direction of engineer in charge of work.	sqm	102.98	Rupees One Hundred Two And Paise Ninety Eight Only
11	327.08	Providing Groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine generator and HOM of machinery including cost of blade, coolant etc., including cleaning aof groove & providing sand and hot bitumen fillars and filler metal etc.,including cost of conveyance of all materials, labour,lead and lift charges and all the other incidental charges as per drawing and as per specifications, MORTH specification and as per the direction of engineer in charge of work.	m	131.59	Rupees One Hundred Thirty One And Paise Fifty Nine Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Contractor

Executive Engineer
Project Division